

MAR 9 1 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
1993 DEC 29 AM 9:43

For corners in Wexford
(County)

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>9W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-4) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor, Sugar 11" S 16 1/2" W 33 links, Hemlock 13" N 67° W 15 links
- M-4) 1894 Teed, Liber 1, page 252, lost, reset on line between NE corner and Southeast corner at 1/2 distance, Elm 14 S 12° E 92, Cherry 4 N 17° W 68
- M-4) 1957 MDOT Plans Project 57-1 #1, corner not described, witnesses, S 10-47 W 109.5', 14" Elm S 57°-12 W 37.4', 8" Elm S 62°47' W 44.9, 10" Elm N 0°-44' W 49.97 3/4" Iron pipe, S 0°-44' E 49.97 3/4" Iron pipe
- M-4) 1968 MSHD Gov't monument witness record, set 9/16" copper welding rod, measured accurately from 1/4 corner 2644.25 and then found 3/4" pipe South 49.97 2' under surface, and 3 old witness trees from MDOT Plans, Project 57-1 #1
- M-4) 1985 Wilcox survey in Section 7, T23N, R8W, Liber S-2, page 226: Found 9/16" rod
- M-4) 1990 Wade-Trim/Granger survey: Found 2" Iron in monument box N 55° E stop sign 61.25, S 30° E stop sign 49.18, N 30°W stop sign 61.45, S 15°W 28" Elm stump 109.55

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-4) 1/4 Section corner common to Section 12, T23N, R9W and Section 7, T23N, R8W

Found 9/16" Iron in monument box centerline roads North-South and 4' South centerline roads East and West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.


Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4) Set 5/8" x 36" Iron with Wexford County brass cap stamped: E 1/4 12, PS 33989, 1993

- N 50° E - 61.25 - Stop sign
- S 15° W - 109.55 - 28" Elm stump
- S 78° W - 64.78 - SE corner concrete box culvert
- N 64° W - 68.58 - Top center 12" CMP culvert
- S 30° W - 59.65 - Iron/Cap 24617



Signed by *Richard D. Wilcox* Date 11/29/93
Surveyor's Michigan License No. 33989