

SUBJECT
RECORDED

MAR 31 1994

RECEIVED

1993 DEC 29 AM 9:43

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Wexford Located in: _____ Corner Code ##
(County)

1. Public Land Survey T 23N R 9W M-5
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-5) 1838 GLO Section post by John Brink, Deputy Surveyor, Sugar 10" S 65° W 69, 10" N 5 1/2° W 26
- M-5) 1892 Teed survey in Section 13: Liber 1, page 253 Sugar 20" S 19° E 28 links
- M-5) 1894 Teed survey in Section 12: Liber 1, page 252, stake Sugar 2 N 37° W 69 links, Elm 64 3/4 E 109 links
- M-5) Wexford County Road Commission: 1/2" rod, 30" Poplar N 80° W 37.84, 24" Maple N 40° W 42.43, Power pole S 40° E 62.553
- M-5) 1993 Wade-Trim survey in Section 13: 1/2" Iron & cap, S 36° W Power pole 40.81, S 60° E Power pole 62.85, N 65° E Yield sign 64.25, N 25° W 30" Maple 42.70

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5) Section corner common to Sections 12, 18 and 7, 13, T23N, R8W
Found Iron and cap 10' West of centerline of a North-South road and ±2' South of centerline of a road to the West and 5' South of tree line to the West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5) Set 5/8" & 3/6" Iron with Wexford County brass cap stamped SE, 12, P533989, 1993
S 40° W - 40.83 - Power pole
S 56° E - 62.73 - Power pole
N 72° E - 64.25 - Yield sign
N 22° W - 42.70 - 30" Maple
N 14° W - 60.18 - 26" Maple



Signed by *Richard D. Wilcox*

Date 11/29/93

Surveyor's Michigan License No. 33989