

SURVEY & RECORD

MAR 8 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 29 AM 9:43

RECEIVED

For corners in

Wexford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>9W</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-6) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, Beech 6" S 72 1/2° W 70, Sugar 10" N 39 1/2° W 17
- M-6) 1892 Teed survey in Section 13: Hemlock 24" N 36° E 39 (Liber 1, page 253)
- M-6) 1973 Wilcox survey in Section 13: Wexford Co. monument N 55° W 43.56 6" Maple, S 35° W 65.18 14" Tri-Maple (Liber 2, page 558)
- M-6) 1977 Wilcox survey in Section 13: (Liber 1, page 549), Wex. Co. mon. N 55° W 6" Maple 43.56, S 35° W 14" Tri-Maple 65.18
- M-6) 1993 Wade-Trim survey in Section 13: Wexford Co. monument S 84° E fence post 61.75, N 39° W 8" Maple 50.50, S 55° W 10" Maple 43.56, S 35° W 65.18 20" Tri-Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- M-6) 1/4 Section corner common to Sections 13, and 18, T23N, R8W  
Found Wexford County monument (bad shape) ±2' West of centerline of a North-South road and ±32' East of a North-South fence. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6) 5/8" x 36" Iron with Wexford Co. brass cap stamped: E 1/4, 13 PS 33989, 1993  
S 80° E - 61.79 - Fence post  
N 35° W - 50.48 - 8" Maple  
S 39° W - 64.90 - 14" Tri-Maple  
N 59° W - 44.26 - 6" Maple



Signed by *Richard D. Wilcox* Date 11/29/93  
Surveyor's Michigan License No. 33989