

MAR 31 1994

RECEIVED

1993 DEC 29 AM 9:43

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Wexford (County) Located In: Corner Code #

1. Public Land Survey T 23N R 9W M-7
T R
T R
T R

2. Property Controlling in Section S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |

A. Description of original monument and accessories and/or subsequent restoration:

- M-7) 1838 GLO Section post by John Brink, Deputy Surveyor, Beech 10" S 78° W 3, Beech 6" N 25° W 66
- M-7) 1972 Wilcox survey in Section 18, T23N, R8W, Liber S-1, page 47, Found 1/2" Iron and cap S 50° W 30.23 Road sign, S 50° E 353.36 road sign, N 45° W 40.98 underground tele riser N 45° E 63.60 4" Pine
- M-7) 1973 Roser survey in Section 13: 1/2" Iron in center of road intersection as recovered by Wilcox tele pole N 37° W 39.5'
- M-7) 1977 Wilcox survey in Section 13: Liber 1, page 549, 1/2" Iron S 50° W 30.23 road sign, S 50° E road sign 35.36, N 45° W tel riser 40.98, N 45° E 4" Pine 63.60
- M-7) 1993 Wade-Trim survey in Section 13: 1/2" Iron, N 38° E 12" Red Pine 63.66, N 66° W 4" Twin Elm 64.68, S 50° W road sign 42.65, S 47° E face phone ped. 36.57

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-7) Section corner common to Sections 13, 24 and 18, 19, T23N, R8W Found Iron & cap in centerline of North, South, East West roads. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-7) 5/8" x 36" Iron with Wexford Co. brass cap stamped: SE 13, PS 33989, 1993
N 41° E - 63.66 - 12" Red Pine
N 63° W - 64.68 - 4" Twin Elm
S 44° E - 36.57 - SW corner face phone pad
S 56° W - 52.75 - 4" Elm



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989