

SUPPLEMENT
RENOVATED

MAR 8 1994

COMMISSION

RECEIVED

LAND CORNER RECORDATION CERTIFICATE 1993 DEC 29 AM 9:43
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wexford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 23N R 9W M-8
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-8) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor
Birch 8" S 68° W 9, Sugar 12" N 55° W 17
- M-8) 1894 Teed survey in Section 24: Beech 6" S 83° E 24, (Liber 1, page 268)
- M-8) 1973 Roser survey in Section 24: Liber 1, page 288, Set DNR monument, Maple 26" S 13° E 64.10, Cherry 8" N 21° E 73.30, Cherry 5" S 76° E 69.40, set loc. tag on fence post N 80° E 25, Reset corner by physical evidence

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- M-8) 1/4 Section corner common to Sections 24, and 19, T23N, R8W
Found DNR monument 1.2' below road surface and ±1' West of centerline of a North-South road and in line with a downed fence to the West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8) Standard DNR monument on 1" pipe
S 16° E - 63.95 - 28" Maple
S 73° E - 69.25 - 8" Tri-Cherry
S 37° W - 30.78 - 6" Poplar
N 37° W - 118.75 - 5" W. Birch



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989