

SUPPLY A
REGISTRATION

MAR 8 1 1994

COMMISSION

RECEIVED

1993 DEC 29 AM 9:43

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Wexford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>9W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-11) 1838 GLO Section post by John Brink, Deputy Surveyor, Maple 12" S 75° W 10, W. Pine 12" N 25° W 6
- M-11) 1883 Teed survey in Section 25: Hemlock 20" N 28 1/2° W 25 links (Liber 1, page 269)
- M-11) 1973 Roser survey in Section 25: DNR monument, 14" Oak S 82° W, 67.5', 14" Oak N 41° W 69.5', 9" Tamarack S 43° E 33.7', loc. tag on 16" Tri-Oak West 66, North-South random line, West 27'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- M-11) Section corner common to Sections 25, 36, and 31, T23N, R8W
Found DNR monument and marker post under water. Corner is in low wet area. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11) Standard DNR monument on 1" pipe
S 85° W - 67.59 - 24" Oak
N 38° W - 69.73 - 20" Oak
S 42° E - 34.13 - 12" Tamarack
N 86° W - 66.00 - Loc. tag on 18" Tri-Oak
N 05° W - 86.13 - 5" Oak



Signed by *Richard D. Wilcox*
Surveyor's Michigan License No. 33989

Date 11/29/93