

MAR 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 9:43

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 23N R 9W M-12
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, Y. Pine 16" S 70° W 18, Hemlock 10" N 1° W 57

M-12) 1973 Roser survey in Section 36: 1 1/4" x 9" pipe and Cedar post w/ loc. tag, 18" W. Pine S 65° W 59.2', 18" W. Pine N 65° W 45.6', 12" W. Pine N 50° W 58.9', ctr. dirt trail rd. (on curve) N 50° E 37'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-12) 1/4 Section corner common to Sections 36 and 31, T23N, R8W
Found 1 1/4" pipe w/ loc. marker ±51' West of centerline of road and ±47' Southwest of centerline of same road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12) Set 5/8" x 36" Iron with Wexford Co. brass cap stamped: E 1/4, 36 PS 33898, 1993
S 66° W - 59.68 - 26" White Pine
N 72° W - 46.35 - 18" White Pine
N 48° W - 59.15 - 12" White Pine
N 50° E - 43.00 - Centerline of trail
N 15° W - 8.57 - 2" Maple
S 10° E - 40.98 - 5" Fir



Signed by Richard D. Wilcox Date 11/29/93
Surveyor's Michigan License No. 33989