

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 23 N.R. 10 W.  
T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 4 - 33

CORNER MONUMENT Drove 1" x 24" pipe below road surface

DATE MONUMENT PLACED AND WITNESSED May 1, 1963

WITNESSES TO CORNER.....



8" Cedar S 44 W 55.8'

8" Cedar N 34 W 54.9'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was established while making a survey of Section 33. Set corner in line with fences north and south, on line between section corners. Unable to locate any previous corner in road fill--probably destroyed in construction. It was felt that the fences of long standing very likely originated at the corner. Of some significance is the fact that a shortage of about 1:40 chain in the entire mile, can be isolated in the E 1/2 mile by acceptance of the fence lines. Proportionate measurement does not lend itself to present occupation any more so than this restoration. See subdivision map and minutes of survey for further information.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Oetting* DATE June 21, 1963  
REGISTERED LAND SURVEYOR #10068