

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Wexford
(County)

Located In:

Corner Code #

RECEIVED

1996 DEC 13 PM 3: 32

Linda Lounsbiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

- | | | | | | | |
|--------------------------------------|---|------------|---|------------|-------------|-------|
| 1. Public Land Survey | T | <u>23N</u> | R | <u>10W</u> | <u>F-13</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George D. Smith, in a field survey on July 26, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Sugar 9 N 66° E 41, Sugar 9 N 40° W 06
1908 D.E. Teed Survey, Liber 1, Page 295 found stake set by Devoc Elm 12, N 73° W 9.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-13) Found 1" pipe 2.5' deep in centerline road East-West and in fence lines North-South. This corner is accepted as the best available evidence of the position of the original corner being the 1/4 corner common to Section 33, T23N, R10W and Section 4, T22N, R10W.

SURVEY &
REMONUMENTATION
MAY 20 1997
COMMISSION

Peer Group Reviewed and Approved
Date: 14 Nov 96
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13) Raised 1" pipe with 5/8" x 24" iron with Wexford Co. Brass cap stamped S 1/4 33, 1996 PS 39098.
- N 45° W - 44.30' - 18" Maple
N 22° E - 41.71' - Power Pole
S 12° W - 35.54' - 24" TW Maple
S 40° W - 58.08' - Power Pole



Signed by George D. Smith
Surveyor's Michigan License No. # 39098

Date 11-21-96