

LAND CORNER RECORDATION CERTIFICATE MAY 20 1997
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wexford Located In: _____ Corner Code # _____
(County)

1. Public Land Survey	T	<u>23N</u>	R	<u>10W</u>	<u>H-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

NON-RECEIVED
 RECEIVED
 1996 DEC 13 PM 3:33
Linda Loughmiller
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, George D. Smith, in a field survey on November 8, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Beech 8 N 64 1/2° E 74, Lynn 8 N 46° W 43
 1984 Mitchell PS#28417, LCRC, Liber 03, Page 345, set Wexford County Monument by proportionate measurement and on line with corners 1/2 mile to West and 1 mile to East, N 15° E 8', Maple 31.80', N 70° E 8' Maple 28.07', S 38° E 12" TW Maple 27.50', S 70° W 6" Maple 42.97'.
 1987 Wilcox Survey by J. L. Wilcox, RLS #14102, Liber 2, Page 362 found Wexford County Monument (witnesses on the survey are incorrect)
 1992 Wade Trim Granger Survey by J. Ray PS #25869, Liber 72, Page 134, found Wexford County Monument (witness on the survey are incorrect).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-13) Found corner set by Mitchell PS #28417 in 1984 position of corner not accepted. This corner was set by single proportionate measurement between corners 1/2 mile to West and 1 mile to East, position of corner 1 mile to East was not accepted. Reset corner by single proportionate measure between re-established corner 1 mile to East and accept corner 1/2 mile West. This position is accepted as a careful and faithful re-establishment of the position of the original corner being the 1/4 corner common to Section 34, T23N, R10W and Section 3, T22N, R10W.

Peer Group Reviewed and Approved
 Date: 14 Nov 96
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-13) Pulled Wexford Co. Mon. and set 5/8" x 36" iron with Wexford Co. Brass cap stamped S 1/4 34, 1996 PS 39098 at new location of corner.

S 60° W - 44.63' - 8" Red Pine
 S 23° E - 35.32' - 8" Tw. Maple
 N 90° E - 28.97' - 8" Maple
 N 30° E 25.59' - 10" Tw. Maple
 West 60± Centerline North-South 2-Trk



Signed by George D. Smith
 Surveyor's Michigan License No. #39098

Date 11-21-96