

LAND CORNER RECORDATION CERTIFICATE MAY 20 1997
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in Wexford
 (County)

Located In:

Corner Code #

- | | | | | | | |
|--------------------------------------|---|------------|---|------------|-------------|-------|
| 1. Public Land Survey | T | <u>23N</u> | R | <u>10W</u> | <u>I-13</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

RECEIVED
 1996 DEC 13 PH 3: 33
Linda Loughmiller
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, George D. Smith, in a field survey on July 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Beech 11 N 25 1/2° E 34, Beech 12 N 48° W 50
- I-13) 1984 Mitchell PS#28417, LCRC, Liber 03, Page 345, set Wexford County Monument by proportionate measurement and on line with corners 1/2 mile to East and 1 mile West, S 15° E 6', Maple 5.00', S 32° W 12" Maple 17.04', S 46° W USFS post 14.9' N 28° W 3" Maple 12.25", N 48° E 8" Maple 29.43'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13) Found corner set by Mitchell PS #28417 in 1984, position of corner not accepted. This corner was set by single proportionate measurement between corners 1/2 mile to East and 1 mile West, position of corner 1/2 mile to East was not accepted. Reset corner position by single proportionate measurement between re-established corner 1/2 mile to East and accepted corner 1 mile West. Position of corner falls in old fence line to South and is accepted as a careful and faithful re-establishment of the position of the original corner being the Section corner common to Sections 34 and 35, T23N, R10W and Sections 2 and 3, T22N, R10W.

Peer Group Reviewed and Approved

Date: 11 Nov 96
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-13) Set 5/8" x 36" iron with Wexford Co. Brass cap stamped: SE 34 1996, PS 39098, in line with fence to South.
 S 45° E - 13.40' - 8" Maple
 S 58° E - 1.23' - 8" Maple
 S 89° W - 22.94' 12" Maple
 N 63° E - 35.31' 10" Maple



Signed by George D. Smith
 Surveyor's Michigan License No. #39098

Date 11-21-96