

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAY 2 1997

Table with columns: For corners in Wexford (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

COMMISSION RECEIVED

1996 DEC 13 PM 3: 33

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. Contains numbers 1-35 and a dot in cell K13.

I, George D. Smith, in a field survey on November 8, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Beech 8 N 48° W 34, Beech 12 N 21° E 28
1886 A.J. Teed Survey, Liber 1, Page 296, found stump of one witness and good stake, no witnesses given
1894 A.J. Teed Survey, Liber 1, Page 173 found old stake ok, Sugar 4 S 42°W 58L.
1901 D.E. Teed iron with brick around it, Sugar 14 S 68° E 105 1/2 L. Sugar 8 S 4 1/2° W 57 1/2
1988 Barnett RLS #13923, Certificate of Survey, Liber 67, Page 529 found 1/2" re-rod W/RLS cap maple 26' S 40°W 70.95 TW 8" Maple N 16° E 38.00', Fence Post S 30° E 23.60' Centerline North-South Road 15' West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-13) Found 1/2" iron set by single proportionate measure by Barnett RLS #13923 corner position not accepted. Reset corner by 1 of DE Teed's 1901 witness trees (Sugar S 68° E 105 1/2 L), dug large hole at this location but could not locate iron with brick around it, intersection has been built up. Position of corner falls in centerline of roads North and East-West and 2.5' West of Centerline Road South, and fits large maple trees along Right-of-Way very well. This position is accepted as a careful and faithful re-establishment of the position of the original corner being the section corner common to Section 35 and 36, T23N, R10W and Sections 1 and 2, T22N, R10W.

Peer Group Reviewed and Approved

Date: 14 Nov 96
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13) Set 5/8" x 36" iron with Wexford County brass cap stamped SE 35 1996 PS 39098.
S 58° E - 50.25' - 30" Maple
S 30° W - 65.36' - 36" Maple
S 70° W - 88.21' - 24" Maple
N 40° E - 40.31' - 8" Maple (Clump)
S 68° E - 69.63' - Remains of Maple tree - witnesses - Teed 1901



Signed by George D. Smith
Surveyor's Michigan License No. #39098

Date 11-21-96