

SURVEY & REMONUMENTATION

RECEIVED

1994 NOV 23 PM 3: 53

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTERED DEEDS

For corners in

Wexford
(County)

COMMISSION Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>23N</u> R <u>10W</u> | <u>M-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, George D. Smith, in a field survey on August 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-6) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, Sugar 14 S 2°W 54, Sugar 13 N 43° W 13
- M-6) 1985 Wade-Trim/Granger LCRC, Liber 03, page 333, set 1/2" iron in centerline road opposite old fence line West, N 51° E 24" Apple 48.00', N 32° W 14" stump 37.52', S 9° W 18" Maple 105.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Wexford County monument (good condition) in centerline roads North-South and opposite old fence West. This corner is accepted as a careful and faithful reestablishment of the position of the original corner, being the 1/4 corner common to Section 13, T23N, R10W and Section 18, T23N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wexford County monument with aluminum cap

- N 51° E - 47.96' - 24" Apple
- S 9° W - 105.72' - 18" Maple
- S 20° W - 129.12' - Power pole
- N 75° E - 62.92' - 6" Ash

Peer Group Reviewed and Approved

Date: 11-21-94

Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by *George D. Smith*
Surveyor's Michigan License No. 39098



Date 11/17/94