

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED

1994 NOV 23 PM 3: 53

For corners in **COMMISSION**

*Linda Longmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Wexford (County) Located In: Corner Code #

1. Public Land Survey T 23N R 10W M-7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, George D. Smith, in a field survey on August 9, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-7) 1838 GLO Section post by John Brink, Deputy Surveyor, 18" Sugar S 44° W 31, 9" Beech N 30° W 14
- M-7) 1853 V.W. Caukins, Deputy Surveyor, Found post, 12" Beech S 45° E 42, 12" Beech S 12° E 85
- M-7) 1973 Griffin LCRC Liber 1, page 473, Found 2" pipe .5' below ground at intersection of trail roads North-South and East-West. Replaced pipe with 6" x 3' concrete monument with 3" brass cap stamped T23N-R10W, R9W S13, S7, S24, S18, 1962. 6" Maple S 37° E 64.00', 14" Maple S 65° W, 38.20', 14" Maple S 37° E, 69.60', 6" Maple N 60° W 50.50'.
- M-7) 1977 Wilcox Certificate of Survey, Liber 1, page 610 and Liber 1, page 540. Found Forest Service monument
- M-7) 1984 Wade-Trim LCRC Liber 1, page 332, Found Forest Service monument, 6" x 3' concrete monument with 3" brass cap N 43° W 8" Maple 20.82', S 68° W 12" Maple 38.30', S 19° E 12" Maple 20.58', East 5" Maple 28.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found U.S. Forest Service monument, 6" x 3' concrete monument with 3" brass cap at intersection of trail roads North-South and East-West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner, being the Section corner common to Sections 13 and 24, T23N, R10W and Sections 18 and 19, T23N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

U.S. Forest Service monument, 6" x 3' concrete monument with 3" brass cap stamped T23N-R10W, R9W, Section 13, Section 7, Section 24, Section 18, 1962

N 43° W - 20.78' - 8" Maple  
 S 24° E - 26.50' - 14" Maple  
 S 66° W - 38.16' - 14" Maple  
 East - 28.75' - 5" Maple



Peer Group Reviewed and Approved

Date: 11-21-94  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith Date 11/17/94  
 Surveyor's Michigan License No. 39098