

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford (County)	Located In	Corner Code #
1. Public Land Survey	T 23N R 10W G6	
2. Property Controlling in Section	T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Craig W. McVean, in a field survey on May 24, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G6 – 1852 – GLO Resurvey - L. S. Scranton – Set Beech ¼ Post
 1) Hemlock 14" N82°W 57 lks
 2) Sugar Maple 18" S67°E 10 lks
 Old ¼ Sec. Cor. is 1.47 Chs. South and 4.48 Chs. West
 - 1885 – CSR - FB 63, p. 1-3 – A. J. Teed –
 Notes GLO Witnesses only.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G6 – ¼ Corner common to Sections 15 & 16, T23N, R10W - Searched in area for GLO evidence, found a few possible Hemlock stumps, but nothing conclusive. Set 4" aluminum DNR cap on 1" x 36" galvanized iron pipe by Single Proportion to GLO as follows; measured grid distance N1°49'21"E 2618.21' (2640'-GLO) to 'G5' and S1°49'21" W 2618.21' (2640'-GLO) to 'G7'. DNR Mon. is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G6 – Stamped 4" aluminum DNR cap on 1" x 36" galvanized iron pipe. Placed cobble stones at bottom of pipe and ring of stone around cap.

N35°E 36.22' to set nail and tag in northwest side 14" Sugar Maple scribed 'XBT'
 S63°E 45.70' to set nail and tag in south side 10" Sugar Maple scribed 'XBT'
 S62°W 59.89' to set nail and tag in north side 12" Sugar Maple scribed 'XBT'
 N56°W 38.47' to set nail and tag in south side 14" Sugar Maple scribed 'XBT'
 Set Blue Carsonite Post 1' North



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/11/2007