

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Wexford (County)

1. Public Land Survey	T	<u>23N</u>	R	<u>10W</u>	<u>J6</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_  
5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on June 6, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J6 – 2000 -- Rec. Survey L. 80, p. 168 - T. G. Hall  
Set 1/2" Rod and cap #33977  
S88°W 41.17' - 12" Elm  
N07°W 18.34' - 16" Beech  
N06°E 10.18' - 5" Maple  
S22°W 9.18' - 8" Twin Maple

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J6 – Center 1/4 corner of Section 14, T23N, R10W - Fd. 1/2" x 18" capped iron rod #33977 in ± E-W fence remains. N-S Fence remaining are 7± East. Fits calculated intersection of 1/4 lines closely. Fd. 1/2" x 18" capped iron rod accepted as best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J6 – Replaced fd. 1/2" x 18" capped iron rod with stamped 2" Aluminum cap on 5/8" x 34" rebar  
N56°E 10.15' to set nail and tag at found nail in NW side 6" Sugar Maple (TGH)  
N13°W 18.20' to set nail and tag at found nail in NE side 16" Beech scribed 'XBT' (TGH)  
S82°W 41.14' to found nail in S side 14" Ash (TGH)  
S15°W 9.18' to set nail and tag at found nail in W side 11" Sugar Maple (TGH)  
S73°E 24.48' to set nail and tag in N side 11" Beech scribed "XBT"  
N85°E 8.3' to Fd. 1 1/4" iron pipe, up 4' above ground  
Set Blue Carsonite Post with location tag 1' NE



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 2/6/2008