

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In _____ Corner Code # _____
(County)

1. Public Land Survey	T _____	R _____		
	T _____	R _____		
2. Property Controlling in Section	S <u>14</u>	T <u>23N</u>	R <u>10W</u>	<u>7</u>
	S <u>13</u>	T <u>23N</u>	R <u>10W</u>	<u>16</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____	
	S _____	T _____	R _____	

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 6, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

7 - None

16 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

7 - N 1/16 common to Sections 13 & 14, T23N, R10W - Set stamped 2" Aluminum cap on 5/8" x 34" rebar per standard BLM procedure, 5' West of centerline N-S gravel Rd.

16 - E 1/16 common to Sections 13 & 24, T23N, R10W - Set stamped 2" Aluminum cap on 5/8" x 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

7 - Stamped 2" Aluminum cap on 5/8" x 34" rebar
S25°E 75.40' to set nail and tag in W side P.P.
N37°E 58.53' to set nail and tag in SE side 14" Sugar Maple
S27°W 116.58' to GPS 'base station' being a 2" Aluminum cap on 5/8" x 34" rebar set in concrete with orange carsonite post 1' North
West 33.00' to set 2" Aluminum cap, stamped - 'ROW', on 5/8" x 34" rebar with cedar guard post with location tag

16 - Stamped 2" Aluminum cap on 5/8" x 34" rebar
N41°W 28.88' to set nail and tag in W side 16" Sugar Maple
N82°W 79.10' to set nail and tag in N side 15" Sugar Maple
S23°W 81.08' to set nail and tag in W side 10" Red Pine
N18°E 35.67' to set nail and tag in W side 14" Sugar Maple
Set Blue Carsonite Post with location tag 1' NW

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 2/6/2008