

SURVEY & REMONUMENTATION

FEB 11 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WEXFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>12W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
RECEIVED
1997 DEC 11 AM 9:28
1997 DEC 11 AM 9:28
Linda Loggins Miller
WEXFORD COUNTY REGISTER OF DEEDS
WEXFORD COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, CRAIG J. PULLEN, in a field survey on MAY 20, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-13 1838 G.L.O. SURVEY BY J. BRINK, WOOD POST BEECH 12 N45E 7, W. PINE 18 N71W 53
- 1988 J. L. WILCOX & ASSOC. SURVEY BY D. SCHRIPEMA PS #24617 L. 67, P. 354 FOUND 1/2" IRON PIPE, SET WEXFORD COUNTY MONUMENT N35°W 50.39' 12" MAPLE, N03°E 32.96' IRON STAKE, N35°E 39.86' 3" OAK, S41°W 44.88' 6" MAPLE
- 1996 MITCHELL & ASSOC. SURVEY BY D. GRIER, PS #33978 L. 75, P. 837, FOUND IRON, MAPLE 12" N35°W 50.39' IRON BAR NORTH 1 32.96', OAK 3" N35°E 39.85', MAPLE 6" S41°W 44.88'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-13 FOUND WEXFORD COUNTY MONUMENT IN GOOD CONDITION 10.5' SOUTH OF CENTERLINE OF 14 ROAD AND 3 PREVIOUS WITNESSES. ALSO FOUND OLD CEDAR POST S12°W 21'. THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13 1/4 CORNER COMMON TO SECTION 33 T23N, R12W, AND SECTION 4, T23N, R12W WEXFORD COUNTY MONUMENT STAMPED: CJP, 39095, 1997, 33, 4, 1/4
- N37°E 6" WHITE OAK 44.87'
- S15°W 10" RED PINE 53.82'
- S44°W 9" MAPLE CLUMP 44.84'
- N32W 14" MAPLE 50.41'
- N4°E FACE OF OLD PLOW BLADE 33.00'

Peer Group Reviewed and Approved
Date: 30 Oct 97
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor



Signed by Craig J. Pullen
Surveyor's Michigan License No. 39095

Date 2 DEC 97