

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED

1994 DEC -9 PM 2: 58

**COMMISSION**

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in

WEXFORD (County)

Located In:

Corner Code #

|                                    |   |     |   |     |     |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey              | T | 23N | R | 12W | M-6 |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
| 2. Property Controlling in Section | S |     | T | R   |     |
|                                    | S |     | T | R   |     |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |     |
|                                    | S |     | T | R   |     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, CRAIG J. PULLEN, in a field survey on JUNE 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-6 1838 GLO SURVEY BY J. BRINK, WOOD POST SUGAR 13 S24W 11 BEECH 7 N16W 30
- 1973 J. ERICKSON PS #16929 FOUND 1" IRON, ACCEPTED AS E 1/4 CORNER. N35°W 56.10' 12" MAPLE N45°E 51.47' T. POLE S35°W 53.74' 7" MAPLE
- 1977 F. THOMPSON PS #21996 L.C.R.C. L.3 P.140 AND WILCOX SURVEY L.1 P.539 FOUND 1" PIPE, SET WEX. CO. MON. WITNESSES SAME AS 1973.
- 1982 J. GAVIN PS #21568 L.C.R.C. L.3 P.268 FOUND WEX. CO. MON. TRIPLE 6" TO 12" MAPLES S70°W 76.31' 14" MAPLE N20°W 67.78' T. POLE N45°E 51.35'
- 1986 WILCOX ASSOC. PS #14102 SURVEY L.2 P.196 WEXFORD COUNTY MONUMENT WITNESSES SAME AS 1973
- 1993 WILCOX ASSOC. SURVEY L.72 P.247 J.D. GEERS PS #33977 WEXFORD COUNTY MONUMENT S50°E 63.95' CTR PHONE RISER #C262 S32°W 61.62' COR. FEN. POST S47°W 50.72' 4" MAPLE N22°W 85.12' 6" MAPLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-6 FOUND WEXFORD COUNTY MONUMENT IN GOOD CONDITION AND 4 PREVIOUS WITNESSES IN CENTERLINE NORTH, SOUTH, EAST, WEST ROADS. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER, BEING THE 1/4 CORNER COMMON TO SECTION 13, T23N, R12W, AND SECTION 18, T23N, R11W.

Peer Group Reviewed and Approved

Date: 12-2-94  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 EAST 1/4 CORNER, SECTION 13, T23N, R12W
- WEXFORD COUNTY MONUMENT
- S42°E CORNER FENCE POST 52.50'
- S30°W CORNER FENCE POST 61.68'
- N22°W 6" MAPLE 85.12'
- S43°W 4" MAPLE 50.72'
- S53°E CENTER PHONE RISER 63.95'



LIBER 04 PAGE 300

Signed by *Craig J. Pullen*

Date NOVEMBER 22, 1994

Surveyor's Michigan License No. 39095