

SURVEY & REMONUMENTATION

FEB 11 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____
For corners in Wexford (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>23N</u>	R	<u>12W</u>	<u>M-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED
1997 DEC 11 AM 9:33
Richard D. Wilcox
WEXFORD COUNTY, MI
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, George Smith, in a field survey on 8-22, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-13) 1837 GLO 6 mile post by John Brink, Deputy Surveyor; Sugar 12 N31°W 15, Sugar 11 S36°W 43
- 1904 A.J. Teed Survey, Liber 1, Page 222. Found both Government witnesses okay
- 1909 D. Teed Survey, Liber 1, Page 324. Found iron stake and both Government witnesses okay.
- 1986 Robert Mitchell PS # 28417 LCRC Liber 3, Page 387. Set corner by double of found corners 1/2 and 1 mile to West position across with found Teed corner to the South 1/4 mile. Set 5" sq x 60" concrete monument with brass cap. S15°W 20" Ash 10.87, East 6" Maple 19.64, N82°W 16" Maple 27.92, N55°E 5" Maple 12.34
- 1986 Robert Mitchell PS #28417 Certificate of Survey, Liber 2, Page 189, Set 5" sq x 60" concrete monument


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-13) Found 5" sq x 60" concrete monument as set by Robert Mitchell PS #28417, and 2 witnesses. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the Township corner common to T23N- R11W, T23N- R12W, T22N-R11W and T22N-R12W

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-13) 5" sq x 60" concrete monument with brass disk
 - N60°E 12.39' 6" Maple
 - S85°E 19.64' 7" Maple
 - N80°W 28.04' 20" Maple
 - S15°W 10.92' 24" Ash

Peer Group Reviewed and Approved
Date: 30 Oct 97
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by *George D. Smith*
Surveyor's Michigan License No. 39098


Date 10-30-97