

# SURVEY & REMONUMENTATION

FEB 11 1998

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

Wexford	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T <u>23</u> N R <u>11</u> W	<u>G-13</u>	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

RECEIVED

1997 DEC 11 AM 9:32

Linda Loughmiller

WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, George Smith, in a field survey on 8-26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:**
- G-13) 1837 GLO Section Post by John Brink, Deputy Surveyor; Sugar 14 N59°E 44', Sugar 10, N10½°W 25'
  - 1848 GLO Subdivision T22N-R11W by Orson Lyons, Deputy Surveyor; Sugar 24 S42°W 9' Sugar S36°E 61'
  - 1899 Alderman Survey Liber 1, Page 311, Field Book 83, Page 29. No description of monument found, Basswood 10 N20°W 62'
  - 1966 Griffin RLS #13584 LCRC, Liber 1, Page 464, found 1½" iron pipe at North edge of an East-West Road and in line with old fences North-South, pipe checks well with occupation and with stump hole (Aldermans Basswood wit.) replaced pipe with 5"x 3' cone. monument with 3" brass disk 1' below ground, stamped T23N-R11W, S33, S34, S4, S3, T22N, 1966 RLS #13584, 8" Ash N49°E 78.78', 8" Maple S13°E 53.93', 7" Maple S48W 43.45', 8" Maple N58°W 76.16'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
- A(cont.) 1987 J.L. Wilcox RLS # 14102 Certificate of Survey, Liber 2, Page 371, found USFS monument.  
Witness same as 1966 Griffin's LCRC.
  - 19?? WCRC witness, same as Griffin's LCRC

Found USFS monument and 2 witnesses as set by Griffin RLS #13584, this corner is accepted as the best available evidence of the original corner being the Section corner common to Section 33 and 34, T23N-R11W, and Sections 3 and 4, T22N-R11W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- USFS monument with 3' brass disk ± 4' Nly of centerline trail
- N69°E 15.05' 6" Maple set nail
- S11°E 54.10' 8" Maple, found nail
- S49°W 43.83' 12" Maple, set nail
- N12°W 32.16' 20" Basswood, set nail

Peer Group Reviewed and Approved  
Date: 10-30-97  
Richard D. Wilcox  
Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith  
Surveyor's Michigan License No. 39088

STATE OF MICHIGAN

GEORGE D. SMITH

PROFESSIONAL SURVEYOR

No. 39088

LICENSED PROFESSIONAL SURVEYOR

Date 10-30-97