

SURVEY &  
RECORDS

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1995 DEC 14 PM 3:49

For corners in **COMMISSION**

*Guido Longmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

<u>Wexford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>11W</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George D. Smith, in a field survey on July 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970; the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, Sugar 8 S 40½°W 40 Sugar 16 N 57½° W 14
- 1973 Wilcox Assoc. Certificate of Survey by J.L. Wilcox, PS#14102 Liber 1, Page 67 set ½ iron and cap #14102 by single proportionate measure between found NE corner, Section 13 and found SE corner Section 13
- 1973 Wilcox L.C.R.C. by J. Erickson PS#16929 Liber 02, Page 594 found ½ iron and cap, as set in certificate of survey recorded in Liber 1, Page 67, and replaced with Wexford County Monument S 45° E 16" Elm 45.92; N 45 E 18" Maple 52.87, centerline of N-S road 8; West
- 1983 Wilcox Assoc. Certificate of Survey by J.L. Wilcox, PS# 14102 Liber 2, Page 06, found Wexford County Monument
- 1988 Wilcox Assoc. Certificate of Survey, D.E. Schripsema, PS# 24617 Liber 67, Page 353 found Wexford County Monument, S 45° E 45.92' 16" Elm, N 45° E 52.87' 18" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Wexford County Mon. in poor condition ±8' East of centerline road North-South and 3' North of centerline road East-West, replaced with 5/8" x 36" Iron with Wexford County brass cap. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Peer Group Reviewed and Approved

Date: 12 Dec 95  
Richard D. Wilcox  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron with Wexford County brass cap
- N 42° W 84.40' 5" Cherry
- N 48° E 52.85' 20" Maple
- S 66° W 80.80' 4" Ash
- S 38° E 46.12 18" Elm



Signed by George D. Smith  
Surveyor's Michigan License No. 39098

Date 12-14-95