

RECEIVED

JAN 17 1996

1995. DEC 14 PM 3: 50

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wexford
(County)

Located In:

Corner Code #

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

- 1. Public Land Survey T 23N R 11W M-13
 T R _____
 T R _____
 T R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, George D. Smith, in a field survey on December 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO 6 mile post by John Brink, Deputy Surveyor, Birch 10 S 53 1/2°E 11, Tamarack 10 N 27° W 42
 1893 Devoe Survey for Petition in Section 6, T22N-R10W, Liber 1, Page 175 found large post under crossing log six feet or more in mud, old Tamarack witness was there but nearly decayed, Birch 8, S 35°E 44

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Computed location of Township corner, by double proportionate measure between fd. SE cor. Section 13, T23N-R11W, and found E 1/4 Section 1, T22N-R11W, found South 1/4, Section 31 T23N-R10W and found South 1/4, Section 36 T23N-R11W. This computed location which checks closely with Devoe distances to East and South falls in water ±3 deep and is ±4 East of centerline old road South and ± 20' North of old sunken road East-West, and position of Township corner which was not set is accepted as a careful and faithful re-establishment of the position of the original corner, being the Township cor. common to T23N-R11W T22N-R11W, T23N-R10W and T22N-R10W. Set witness corner on East line Section 1, T22N-R11W 40.00' South of Township corner, and 200' North of Township corner on East line Section 36, T23N-R11W.

Peer Group Reviewed and Approved

Date: B Dec 95
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Witness Corner on East Line Section 36, T23N-R11W, set 5/8" x 36' iron with Wexford County brass cap stamped: Wit. cor. 1995, PS 39098, ±15' West of centerline old sunken road
 N 3° E 34.35' 8" Maple
 S 70° W 18.10' 5" Y. Birch
 N 47° E 45.62' 5" Ironwood
 N 85° W 30.55' 6" Maple
 S 01°37'15" E 200.00 computer loc. of Township cor.
 S 87°00'43" E 2670.02' S 1/4 Sec. 31, T23N-R10W
 S 83°14'26" W 2619.67' S 1/4 Sec. 36, T23N-R11W

Witness Corner on East Line Section 1, T22N-R11W, set 5/8" x 36" iron with Wexford County brass cap stamped: Wit. Co. 1995, PS 39098, ±5' East of centerline old road.
 S 74° W 20.45' 7" Elm
 S 34° W 56.40' 14" Maple
 S 12° E 44.55' 8" Maple
 S 50° W 65.78' 6" Apple
 N 01°59'50" W 40.00' Computed loc. of Township cor.
 S 88°29'49" W 2609.41 S 1/4 Sec. 36, T23N-R11W
 N 87°49'52" E 2661.24 S 1/4 Sec. 31, T23N-R10W

Signed by *George D. Smith*
 Surveyor's Michigan License No. 39098

Date 12-14-95

