

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 24 ^{N.} R. 9 ^{W.}	F-3; G-3
2. PROPERTY CONTROLLING IN SECTION 4 _____	T. 24 ^{N.} R. 9 ^{W.}	8; 10; 14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} ^{S.} R. _____ ^{E.} ^{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on October 9, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument necessary to locate subsequent corners:

C. (continued)	10	14
	Set 1"x36" pipe & cedar post	Set 1"x36" pipe & cedar post
	24" W. Pine S56°W 53.58	w/loc. tag
	10" J. Pine S18°W 20.92	10" B. Cherry N71°E 56.5
	10" J. Pine S68°E 43.68	14" Oak N24°E 47.6
		9" Oak N19°W 52.5

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- F-3 Found Fargo 3/4"x36" pipe & butterdish in place. This corner recovered by M.D.S.H. in 1955.
- G-3 Found Fargo 3/4"x26" pipe & two 3" butterdishes in place.
- 8 Established corner per standard B.L.M. instructions; E-W fence remains approximately 42' north.
- 10 Established corner per standard B.L.M. instructions; old fence corner, fence east and north, is 25' east and 57' south.
- 14 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3	G-3	8
Set Wexford Co. mon. & ced. post	Fd. Fargo pipe & added std.	Set 1 1/4"x36" pipe & ced. post
9" Hemlock S48°E 22.7	Wexford Co. mon. & ced. post	w/loc. tag
9" W. Pine N34°E 38.8	9" Oak N47°E 29.2	6" Oak S52°E 46.22
10" W. Pine N07°E 37.8	9" Oak N79°E 28.8	12" R. Pine N20°W 91.65
Ctr. US-131 Due W 124.8	12" Oak S34°E 26.1	

SIGNED BY Carl F. Roser 3-4-75 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

LIBERTY TOWNSHIP
WEXFORD COUNTY