

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 24 N. R. 9	E-1; E-2; F-1
2. PROPERTY CONTROLLING IN SECTION 4 _____	T. 24 N. R. 9	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 8, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

3
Set 1"x36" pipe; cedar post
w/loc. tag
4" B. Cherry S83°E 123.9
7" J. Pine N15°E 40.7

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-1 Found and accepted 2"x48" pipe in concrete by deceased Department Surveyor M. Schaaf.
- E-2 Restored ¼ corner on line between section corners to north and south, and at prorated distance to U.S. meander.
- F-1 Accepted standard Wexford County monument by R.L.S. J. Wilcox. This corner also recovered by M.D.S.H. in 1955.
- 3 Established corner at proportionate distance to U.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1	E-2	F-1
Fd. Schaaf mon. & added std. Wexford County monument	Set std. Wexford Co. mon. Set ced. post w/loc. tag	Fd. Wexford Co. mon. & set cedar post
14" Oak N81°E 189.8	Due N 33'	7" B. Cherry N38°E 54.9
12" Twn.R.Pine S27°E 173.6	Ctr. E-W dirt trail	Ctr. E-W gravel rd. Due N 34.0
Ctr. E-W sand trail	Due N 2'	Ctr. RR track N88°56'E 74.86
Due S 2'	Old cor. fence post	Ctr. creek 8' wide Due W 78'±
Ctr. fire lane N Due E 15'	S56°W 20.3	
Set ced. post w/loc. tag	8" J. Pine S70°E 38.2	
Due S 33'	5" J. Pine N61°W 33.6	

SIGNED BY Carl F. Roser 3-4-75 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

LIBERTY TOWNSHIP
WEXFORD COUNTY