

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 9 W.	C-9
2. PROPERTY CONTROLLING IN SECTION 30	T. 24 N. R. 9 W.	6; 9; 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on May 7, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - ~~Description of original monument and accessories and/or subsequent restoration.~~
 C. (continued)

- 16
- Drove 1"x18" Solid Iron Rod
- 6" Cedar N10°E 51.14
- 6" Cedar N45°E 53.53
- 30" W. Pine S70°E 54.85
- Set cedar post w/loc. tag
- North 38'
- Ctr. E-W gravel road
- North 5'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-9 Accepted fd. nail (previous iron pin) that was recovered & witnessed by Wexford Co. Rd. Comm. in 1972. Replaced w/Wexford Co. Mon. Ctr. intersection of E-W b'top road & N-S gravel road is 1'± N & 2'± E.
- 6 Set ctr. of NE¼ S-30 per standard BLM instructions. N-S fn. is 45'± West.
- 9 Estab. E 1/8 corner on E-W ¼ line S-30, midway & on line between ctr. & E¼ cor.S-30.
- 16 Established 1/8 corner per standard BLM instructions.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9	6	9
Fd. Wex.Co.Rd.Comm. nail repl. w/Wexford Co. Mon.	Set 5/8"x36" rerod w/RLS Cap & cedar post w/loc. tag	Set 5/8"x36" rerod w/RLS Cap & cedar post w/loc. tag
*15" Twin Maple N55°E 111.40	Power Pole N22°W 46.36	6" Twin Maple N08°W 40.9
*Ctr.MBTC Riser S50°E 51.2	27" W. Pine S68°E 30.8	5" Ironwood S59°E 38.2
*3" R. Pine N45°W 76.46	10" Maple S25°W 32.0	8" Maple S52°W 12.4
Set ced.post w/loc.tag N45°W 47'		
9" R. Pine S40°E 81.08		

* previous rd. comm. witnesses now new side nails
 SIGNED BY _____

Carl F. Roser

DATE 7-23-80



SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

LIBERTY TOWNSHIP
 WEXFORD COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____