

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 24 N. R. 9 W. ●	B-1; C-1
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 11, 1979 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- B-1 Fd. Schaaf mon. & Fargo butter dishes (1913); replaced with Wexford Co. mon. for 1/4 corner common to Sec. 6, T24N-R9W, Wexford Co. and Sec. 31, T25N-R9W, Grand Trav. Co.
- C-1 Fd. Schaaf mon. that fits possible U.S.B.T. remains, white pine stump, N47°E, 62.0'. Corner is in approximate center of E-W dirt road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1	C-1
Set Std. Wexford Co. Mon. & cedar post w/loc. tag.	Fd. Schaaf mon.; replaced w/ Wexford Co. monument.
12" Twin Oak S20°E 26.8 (in young red pine plantation)	20" Oak N55°W 84.8
No other witness available	18" Twin Oak S27°E 65.2
	4" Maple S25°W 39.6
	Set cedar post Due S 33'±

SIGNED BY Carl F. Roser  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 12028  
 FOR STATE AND UNITED STATES AGENCIES:

DATE 1-30-80  
 \_\_\_\_\_  
 \_\_\_\_\_



SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ LIBERTY TOWNSHIP  
 WEXFORD COUNTY