

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>24</u> N. <u>9</u> W. <u> </u>	K-8 /
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. <u>24</u> N. <u>9</u> W. <u> </u>	5, 7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3/8/82, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-8 FD WEXFORD COUNTY MONUMENT PER RLS, J. WILCOX SURVEY OF EAST LINE OF SEC. 23. FARGO HAD TWO U.S. - B.T.'S. (*Wilcox fd. Fargo-1913- Corner for E 1/4 Cor. of Sec. 23*)
- 5 RECOVERED 1/2" ROD IN CONC FOR NW CORNER OF S 1/2 OF NE 1/4 OF SEC. 23 PER RLS, J.W. WILCOX SURVEY AND SEC. SUB'N OF NW 1/4 OF SEC. 23.
- 7 ESTAB N 1/8 COR ON EAST LINE OF SEC. 23 MID-WAY AND ON LINE BETWEEN RECOVERED NE & E 1/4 CORNER OF SEC. 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8	5	7
FD WEXFORD CO MON; ADDED CED POST W/LOC TAG.	FD 1/2" ROD W/CONC. BASE & STEEL FN POST & SET CED POST W/LOC TAG	DROVE 5/8" X 36" REROD W/RLS CAP & SET CED POST W/LOC TAG.
* 6" BALSAM S02°W 23.1	6" CEDAR N55°E 2.8'	6" R. PINE N40°E 70.4
* 12" BIRCH S82°W 12.8	6" CEDAR S35°E 10.0'	9" MAPLE N74°W 26.1
* 8" CEDAR N04°W 7.6	6" CEDAR N65°W 6.6'	12" W. OAK S20°W 24.6
6" MAPLE S66°E 19.9		2-TRACK 12'±
*= J. WILCOX B.T.'S BUT WE FACED AND SCRIBED & PULLED DIST'S TO LOWER FACE.		(NW & SE) EAST

SIGNED BY Carl F. Roser 03-14-83 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

LIBERTY TOWNSHIP
WEXFORD COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____