

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1994 DEC -9 PM 4: 24

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTERED DEEDS

For corners in

Wexford

(County)

Located In:

Corner Code #

- | | | | |
|---------------------------------------|--------------------------|-------------|--|
| 1. Public Land Survey | T <u>24N</u> R <u>9W</u> | <u>D-13</u> | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George D. Smith, in a field survey on August 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- D-13) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, set post, Cedar 12° N 10° W 16, Ironwood 8° N 50° E 18
 - D-13) 1896 A.J. Teed Survey in Section 5, T23N, R9W, Liber 1, page 242, set corner (no description given) Hemlock S 20 3/4° E 83
 - D-13) Wexford County Road Commission witnesses, stake and stones, fence post N 01° E 36.70', fence post S 2° W 33.30' (old witness book)
 - D-13) 1973 Wilcox LCRC, Liber 2, page 540, set Wexford County monument by old Wexford County Road Commission witnesses 4' South of centerline road due South 33.80' fence corner, due North 27.04' fence corner
 - D-13) 1973 Wilcox Certificate of Survey, Liber 1, page 106, set Wexford County monument
 - D-13) 1976 Wilcox Certificate of Survey, Liber 1, page 408, Found Wexford County monument, South fence corner 33.80', North fence corner 27.04'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Wexford County monument with top broken ±4.3' South of centerline of East-West road and in fence lines North and South. This corner is accepted as a careful and faithful reestablishment of the position of the original corner, being the 1/4 corner common to Section 32, T24N, R9W and Section 5, T23N, R9W.

Peer Group Reviewed and Approved:

Date: 12-9-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" Iron with Wexford County brass cap stamped S 1/4 32, 1994, PS 33989

- N 34° W - 34.61' - Railroad tie fence post
- N 4° E - 28.04' - Fence post
- S 35° W - 66.15' - 5" Spruce
- S 17° W - 44.96' - 7" Twin Apple
- S 5° W - 34.20' - Fence post
- S 59° E - 69.37' - 6" Box Elder

LIBER 004 PAGE 316



Signed by *George D. Smith*

Date 12/9/94

Surveyor's Michigan License No. 39098