

RECEIVED

1998 DEC 30 PM 2: 11

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford (County) Located In: Corner Code #
1. Public Land Survey T 24N R 09W M-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, George D. Smith, P.S., in a field survey on May 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Table with 13 rows and 13 columns (A-M) containing numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:


- M-5) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor. Hemlock 10-N23W-11; Hemlock 10-S73 1/2 W-34
M-5) 1853 GLO subdivision of T24N, R8W by Thomas Whelpley, Deputy Surveyor. Maple 10-S53E-31; Hemlock 12-N54 1/2 E-23
M-5) 1913 Fargo Engineering Co. found remains of four US Witness trees and part of old stake. White pine stump 30"-S38E-0.09 1/4; White pine stump 28"-S82 1/2 W-0.53
M-5) 1967 Ostling PS #10068 Michigan Department of Conservation Land Corner Record Liber 1, Page 325 (Miss Co. Records) found Fargo Corner set 1" pipe with 4" aluminum cap. 8" Twin Maple-S57W-48.6; 8" Twin Maple-N30E-24.0.
M-5) 1980 McCombs PS #10696 LCRC Liber 3, Page 240 found DNR Monument. 3" Spruce-N35E-13.23'; 20" Twin Maple-N32E-24.38'; 6" Maple-N60W-31.10'; 12" Birch West 31.47'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR monument as recorded in Liber 1 page 325 (Miss. Co. Records) and 3 witnesses as noted below from an LCRC recorded by McCombs PS #10696 Liber 3, Page 240. This corner is accepted as a careful and faithful perpetuation of the position of the original corner being the section corner common to Section 12 and 13, T24N, R9W and Sections 7 and 18, T24N, R8W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- DNR Monument 1" pipe with aluminum cap
7" Spruce N35E 13.12' (13.23' McCombs)
12" Twin Oak N30E 24.20'
6" Twin Maple N55W 31.08' (31.10' McCombs)
14" White Birch West 31.67' (31.47' McCombs)



Signed by [Signature]
Surveyor's Michigan License No. 39098

Peer Group Reviewed and Approved
Date: 4 December 1998
Richard D. Wilcox, Wexford County Surveyor

Date 12-9-98