

FEB 26 1998

RECEIVED

1998 DEC 30 PM 2: 11

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

SECTION _____
For corners in _____
Wexford
(County)

Located In: _____ Corner Code # _____
T 24N R 09W M-9
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

I, George D. Smith, P.S., in a field survey on May 19, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-9) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor. Birch 10 S76W 13; Cedar 10 N37W 12
- M-9) 1853 GLO Subdivision of T24N, R8W by Thomas Whelpley Deputy Surveyor, Hemlock 10-N42 1/4 E-16; Hemlock 11 S22 1/2 E 19.
- M-9) 1914 E.A. Beuthien Survey in Section 30, T24N, R8W, O.B.O.K. N.B. W.P. 10-S57E-160.
- M-9) 1975 J.L. Wilcox PS #14102 LCRC Liber 2, Page 778, 779 Set corner by retracing old survey along township line. Set Wexford County monument. 14" Birch South 26.10; 5" Twin maple S60E 30.30; 8" Cedar in clump N10E 12.30; North 15' edge of stream
- M-9) 1981 Roser PS #12028 LCRC Liber 3, Page 259. Found and accepted Wexford County monument as re-established by J.L. Wilcox PS #14102, 16" W. Birch South 26.07 10"; Maple S60E 30.30'; 10" Cedar cluster N32E 12.61'; Creek North 16' ±.
- M-9) 1986 J. Ray PS #25869 Cert. of Survey, Liber S-2, Pages 329-330 Miss. Co. Records Corner found no witness given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Wexford County monument and 2 witnesses from 1975 J.L Wilcox PS #14102 LCRC. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the section corner common to Sections 24 and 25, T24N-R9W and Sections 19 and 30, T24N-R8W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wexford County monument with aluminum cap stamped SE 24, 1998, PS 39098.
N35E 13.30' 30" Cedar
S60E 30.41' 6" Twin Maple (30.30 Wilcox)
S05W 26.14' 15" Birch (26.07 Wilcox)
North 15' ± Stream
S75E 24.54' 12" Hemlock

Peer Group Reviewed and Approved
Date: 4 December 1998
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by *George D. Smith*
Surveyor's Michigan License No. 39098

Date 12-9-98

