

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In _____ Corner Code # _____
(County)

1. Public Land Survey	T	<u>24N</u>	R	<u>9W</u>	<u>G4</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	R	_____	_____
	S	_____	R	_____	_____
3. Miscellaneous Property in Section	S	_____	R	_____	_____
	S	_____	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Jan. 19, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G4 – 1852 – GLO – V. W. Caukin – Set ¼ post

- 1) Cedar 18" S50°E 26 L.
- 2) Beech 10" N48°W 18 L.
- 1896 – CSR – A. J. Teed
- 3) W. Pine root S59°E 57 L.
- Big Stone a little SE of corner
- Fd. U.S. wits. and Hemlock station tree
- 1913 – Fargo Engineering – Fd. remains of both US Wits. - set iron and crockery mon.
- 4) Aspen 8" S10½°E 0.86½
- 5) Aspen 6" N36½°W 0.33½
- 1957 – Co. Rd. Comm. – fd. ¾" pipe
- 6) 7" Elm N70°W 92.95'
- 7) 14" Hemlock S17°W 48.19'
- 8) 7" Cedar S20°E 63.61'

- 1995 – C. F. Roser – LCRC, L. 4, p. 345 – found Fargo pipe and butter dishes. Replaced w/ DNR mon. and set Cedar post
- 9) 7" Cedar N27°W 18.90'
- 7) 18" Hemlock S20°W 48.13'
- 10) 9" W. Pine S30°E 48.50'
- 11) 5" W. Pine S25°W 15.44'
- 2001 – J.G. Curtis – LCRC - L.5, p. 348 -
- Fd. DNR Corner disk alongside Cedar Post on bank
- 12) S57°W 8.38' set N & T in 175 mm Balsam
- 13) S38°E 8.70' set N & T in 150 mm Balsam
- 11) S25°W 15.46' fd. nail in 150 mm W. Pine
- 14) N60°W 23.88' set N & T in 75 mm Ash

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G4 – ¼ corner common to Sections 9 & 10, T24N, R9W - Found 4" DNR Aluminum cap on 1" pipe and fits witnesses per C. F. Roser, J.G. Curtis, Wexford Co. Rd. Comm. and Fargo. GLO & Teed witnesses are gone. Edge of River High Bank NW – SE is 6'± NE. DNR monument accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G4 – 4" Aluminum DNR Cap on 1" galv. iron pipe.
 S41°E 8.68' to fd. nail in NE side 8" Balsam (#13)
 S22°W 15.49' to fd. nail in W. side 7" W. Pine (#11)
 S55°W 8.44' to fd. nail in NW side 8" Balsam (#12)
 N33°W 21.90' to set Nail & Tag (N & T) in NE side 22" Poplar (#5)
 N29°W 18.89' to fd. nail in SW side 10" Cedar (#9)
 S13°W 48.16' to fd. nail in W. side 21" Hemlock (#7)
 S29°E 48.51' to fd. nail in SW side 9" W. Pine (#10)
 N57°W 23.94' to fd. nail in SW side 3" Ash (#14)
 S20°E 63.65' to fd. N & T in 12" Cedar stump (#8)
 Set Blue Carsonite Post 1' North
 NW 1.4' to face fd. Cedar post.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 3/15/2007