

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 13 T 24N R 9W 14
S 13 T 24N R 9W 13

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 10, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

13 - None

14 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

13 - SE 1/16, Section 13, T24N, R9W - Set stamped 2" Aluminum cap on 5/8" x 34" rebar per standard BLM procedure.

14 - S 1/16 between Section 13, T24N, R9W and Section 18, T24N, R8W - Set stamped 2" aluminum cap on 5/8" x 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13 - Stamped 2" aluminum cap on 5/8" x 34" rebar
S30°W 31.22' to set N & T in SE side 7" Fir
S72°E 22.12' to set N & T in NE side 7" Fir
N66°E 32.76' to set N & T in N. side 4" R. Maple
N76°W 47.44' to set N & T in S. side 3" J. Pine
Set Blue Carsonite Post with loc. Tag 1' NW

14 - Stamped 2" aluminum cap on 5/8" x 34" rebar
N84°E 21.43' to set N & T in N. side 12" Cedar
S30°E 44.24' to set N & T in NE side twin 20" W. Oak
S63°W 36.28' to set N & T in SE side 8" R. Maple
N22°W 12.24' to set N & T in SW side 7" W. Oak
Set Blue Carsonite Post with loc. Tag 1' NE

Signed by:

Craig W. McVean
Surveyor's Michigan License No.: 39088

Date:

3/15/2007