

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Wexford Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 3 T 24N R 9W 4
 S 3 T 24N R 9W 5

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 2, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1								●					
2	6			5			4	3		2			1
3													
4	7			8			9	10		11			12
5													
6	18			17			16	15		14			13
7													
8	19			20			21	22		23			24
9													
10	30			29			28	27		26			25
11													
12	31			32			33	34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

4 - None 5 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

4 - NW 1/16 Cor., Sec. 3, T24N, R9W - Set stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. 5 - CN 1/16 Cor., Sec. 3, T24N, R9W - Set stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4 - Stamped 2" Alum. Cap on 5/8" x 34" rebar.
 Set Blue Carsonite Post w/ loc. tag 1' SW
 S38°E 68.75' to set N & T in NE side 4" W. Pine
 S20°W 21.20' to set N & T in E. side 2" W. Pine
 N35°W 9.12' to set N & T in NE side 4" W. Cherry
 N10°E 42.97' to set N & T in E. side 4" W. Oak

5 - Stamped 2" Alum. Cap on 5/8" x 34" rebar
 Set Blue Carsonite Post w/ loc. tag 1' SE
 N40°E 21.61' to set N & T in SE 9" J. Pine
 N27°W 8.75' to set N & T in W. side 9" J. Pine
 S20°E 32.50' to set N & T in E. side 7" J. Pine
 S34°W 34.85' to set N & T in SE side 6" J. Pine

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 3/15/2007