

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 20 - 21

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 12, 1962

WITNESSES TO CORNER.....



6" W. Pine N 78 W - 153.7'

8" Balsam S 8 E - 126.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found 1 1/4" pipe and old stake at corner as set by Marcus Schaaf R.L.S. about 1940. Corner previously restored by Fargo Engineering for Consumers Power Company in 1913, at which time they found point of old stake and remains of both U.S. witnesses which are still in place. Corner falls at fence corner N-S-E and checks very well with stream north.

SURVEYOR'S SEAL

SIGNED Kenneth J. Oetting DATE April 20, 1962
REGISTERED LAND SURVEYOR