

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD


T. 24 N. R. 10 W.  
T. 24 N. R. 11 W. Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 30 - 31 - 25 - 36

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 11, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

9" R. Pine S 40 E - 79.3'

5" Maple N 77 W - 18.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in T 24 N, R 10 W. Found 1 1/4" pipe at corner as established by Marcus Schaaf, R.L.S. in 1939. Previously re-stored by Fargo Engineering Company for Consumers Power Company in 1913 from U.S. BTs. Remains of NE Gov't BT and Fargo witnesses still in place.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE April 23, 1962  
REGISTERED LAND SURVEYOR