

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 24 N.R. 10 W.
T. 24 N.R. 11 W. Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19 - 30 - 24 - 25

CORNER MONUMENT Set 1" pipe with 4" brass cap below surface

DATE MONUMENT PLACED AND WITNESSED April 11, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

12" Twin R. Pine S 46½ E - 54.4'
14" R. Pine N 24 W - 80.6'
AND
5" J. Pine S 40½ W - 83.2'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Recovered corner as established by Fargo Engineering Company for Consumers Power Company in 1913. Found crockery in place at corner properly located from SE Fargo witness, but stake or iron removed in road construction. Also, this corner was apparently located and used in a subsequent survey of record by the County Surveyor, whose B. Oak NBT is still in place. Corner falls in road intersection N-S and W.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Belling* DATE April 23, 1962
REGISTERED LAND SURVEYOR