

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY


T 24 N R 10 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 6 - 7

CORNER MONUMENT Set Std. Dept. Mon & Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 7-2-70

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

14" Maple S 73 E 115.8'  
14" Maple S 28 <sup>W</sup> 156.5'  
AND  
E-W Trail Road Due S 16'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished while making a retracement survey in this area. The corner was set at the intersection of a straight line from the N 1/4 and center of Section 6 projected Southerly with a straight line between the SW corner and the SE corner of Sec. 6, which fits the survey of Sec. 6, by E. P. Waterman dated September 1909.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rorer*  
REGISTERED LAND SURVEYOR 12028

DATE 7-17-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68