

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY


T 24 N R 10 & 11 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 & 36

CORNER MONUMENT Set Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 6-23-70

WITNESSES TO CORNER..... 9" Cedar S 42 E 39.4'



5" Cedar S 42 W 25.1'

6" Maple S 08 E 19.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was established equidistant and on line between accepted Section corners to N & S. 'Calls' in U.S. line notes to swamps and streams for this mile appear to be in gross error.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Carl F. Rover

DATE

7-17-70

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68