

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 16 - 21

CORNER MONUMENT Drove 1 1/2" x 2" pipe below surface

DATE MONUMENT PLACED AND WITNESSED April 13, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" Balsam S 9 E - 60.0'

5" Balsam S 67 1/2 W - 78.5'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by proportionate measurement between Section corners while making a survey in this township. Previously set in this manner by Fargo Engineering Company, but could find no corner, and Fargo witnesses gone. Falls at south edge of E - W County Road, and nearly in line with old road north. Best available evidence.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Pelting  
REGISTERED LAND SURVEYOR

DATE April 23, 1962