

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 17 - 20

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 13, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

12" R. Pine N 77 W - 103.2'

7" Maple S 6 E - 29.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found 1" iron pipe in place as established by Fargo Engineering Company for Consumers Power Company in 1913. Corner was established by Fargo by proportionate measurement for lack of U. S. evidence. Both Fargo witnesses in place with marks plain.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Petting* DATE April 23, 1962
REGISTERED LAND SURVEYOR