

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 21 - 28

CORNER MONUMENT Set 1" pipe with 4" Brass cap

DATE MONUMENT PLACED AND WITNESSED April 16, 1962

WITNESSES TO CORNER.....



7" Cedar S 9 W - 3.7'

5" Cedar N 58 E - 17.6'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was established by proportionate measurement between section corners while making a survey in this township. Unable to identify anything for original evidence. An old post bears N 44 W 10', but nothing for U.S. witnesses in place.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Oetting* DATE April 23, 1962  
REGISTERED LAND SURVEYOR