

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16 - 17 - 20 - 21

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 13, 1962

WITNESSES TO CORNER.....



7" Maple N 25 E - 38.6'

7" Maple N 64½ W - 64.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found stake point as established by Fargo Engineering for Consumers Power Company in 1913. Remains of their witnesses in place. This corner was established by proportion in 1913 for lack of government evidence. Checks for measurement to good corners in each direction.

SURVEYOR'S SEAL

SIGNED *Herbert J. Petting* DATE April 23, 1962
REGISTERED LAND SURVEYOR