

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N. R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28 - 33

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 17, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" Cedar N 23½ E - 60.4'

6" Cedar S 57 E - 48.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey in this township. Set corner by proportionate measurement, midpoint on line, between Section corners. Cannot identify Elm U.S. BTs, but this point falls in low swale which obviously supports such species.

SURVEYOR'S SEAL

SIGNED

*Kenneth J. Oething*  
REGISTERED LAND SURVEYOR

DATE April 24, 1962