

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD &
GRAND TRAVERSE COUNTY


T 24 & 25 N R 10 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 6 & 31

CORNER MONUMENT Set Std. Dept. Monument (buried in road shoulder)

DATE MONUMENT PLACED AND WITNESSED 7-2-70

WITNESSES TO CORNER..... 14" Twn. B. Cherry S 72 E 113.7'



14" Triple B. Cherry S 12 W 67.5'

Set Cedar Guard Post Due N 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found angle iron in road shoulder fill above and along side of old 1" pipe. Replaced with Std. Dept. Mon. Corner fits Waterman Survey of Sec. 31, T25N-R10W. Blacktop road on curve is SE'ly 15'. Corner is in line with fence remains to North & South.

SURVEYOR'S SEAL

SIGNED Carl F. Roer DATE 7-17-70
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68