

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


WEXFORD COUNTY  
T 24 N R 10 & 11 W

DESCRIPTION OF CORNER Sec. corner common to Sections 13-18-19-24

CORNER MONUMENT Set Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 6-25-70

WITNESSES TO CORNER.....



14" R. Pine S 45 E 19.4'

7" R. Pine N 02 W 31.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. Found the butter dishes in hole where pipe had been, which fit old Fargo Witnesses. Pipe had apparently been hooked out during pine planting. Accepted Fargo Engineering corner, 1913, as proper NW corner of Section 19, T24N-R10W.

SURVEYOR'S SEAL

SIGNED Carl F. Roer DATE 7-17-70  
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68