

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 30 - 31

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 25, 1962

WITNESSES TO CORNER.....



6" Maple N 26½ W - 28.3'

4" R. Pine S 51 E - 41.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found 1¼" pipe at corner as established by Marcus Schaaf, R.L.S. in 1938 at which time the sites of the U.S. B.T.s were identified. Checks stream crossing east and falls within 4' of proportionate measure location. Considered acceptable.

SURVEYOR'S SEAL

SIGNED *Russell J. O'Leary* DATE April 27, 1962
REGISTERED AND SURVEYOR