

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N. R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 20 - 21 - 28 - 29

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 16, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

18" W. Pine stump N 22 W - 47.2'

7" Maple S 72 E - 42.6'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was found while making a survey in this township. Found 1 $\frac{1}{4}$ " pipe in place as established by Marcus Schaaf, R.L.S. in 1938, from sites of U.S. BTs. Checks stream crossings okay east and west and falls nearly on line over 1/4 and Section corner north. Can find no better evidence of corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Oetting* DATE April 16, 1962  
REGISTERED AND SURVEYOR