

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N.R. 10 W.


Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28 - 29 - 32 - 33

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED April 16, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

10" W. Pine S 79½ E - 84.4'

5" Twin Cedar S 25 E - 54.1'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Found 1¼" pipe in place as established by Marcus Schaaf R.L.S., in 1938, at which time remains of U.S. BTs were evident. Checks swamp edges and stream crossing okay. Used in recent survey to establish S 1/4 corner of Section 29. No better evidence available.

SURVEYOR'S SEAL

SIGNED

*Kenneth J. Betting*  
REGISTERED LAND SURVEYOR

DATE April 24, 1962