

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---------------------------------------|--|--------------------|
| 1. PUBLIC LAND SURVEY | T. 24 N. R. 10 P | E-4 |
| 2. PROPERTY CONTROLLING IN SECTION 9 | T. 24 N. R. 10 P | 6; 7; 9 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. N. S. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 25, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration~~

C. (continued)

- 9
- Set 1"x18" iron rod
 - 8" Red Pine N14°W 70.1
 - 10" Red Pine N51°W 102.4
 - set cedar post w/loc. tag Due N 50 center E-W blacktop co.rd. Due N 7.5
 - 10" tri-Maple S60°W 70.5

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-4 Found concrete monument as placed by J. Wilcox, RLS, Manton, at recovered position of Fargo pipe. Corner falls near foot of steep hill. Got up true E-W ¼ line of Sec. 9 by buck-in on hillside 200'± W of W¼ S-9.
- 6 Established corner per standard B.L.M. instructions.
- 7 Established corner equidistant and on line between NE corner and E¼ of Sec. 9.
- 9 Established 1/16 corner equidistant and on line between center and E¼ of S-9. Old fence to north is 14 ft. west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---------------------------|---|--|
| E-4 | 6 | 7 |
| Concrete sub'n. monument | Set 1½"x36" pipe & cedar post with location tag | Drove 1½"x9' pipe in Silver Cr |
| J. Wilcox witnesses | 7" Thornapple S72°E 69.0 | 11" Cedar S89°W 32.6 |
| 14" Oak S20°W 27.27 | 12" Hornbeam N74°E 99.9 | 8" Cedar N40°E 22.6 |
| 8" Twn. Maple N45°W 7.78 | set 1"x36" pipe S00°33'W 338.10 | 12" Cedar S59°E 16.3 |
| 6" Twn. Maple N50°E 14.55 | set 1"x36" pipe N89°41'E 381.70 | set 1"x36" pipe & cedar post S89°41'W 25.0 |
| | | Right bank of stream E 3'± |


SIGNED BY Carl F. Roser 11-6-75 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

GREENWOOD TOWNSHIP
WEXFORD COUNTY